MYSORE DIVISION.

Notice dated 5th September 1916.

The public are hereby informed that a portion of French Rocks Station-Nelligere road in the 19th mile between the Honakere bridge and Honakere village is closed for the traffic since the road is washed away during the heavy rains in the last week of August. The traffic will have to go in the old road crossing the river where it is not bridged.

Notice.

The attention of the public is invited to the advertisement in detail published in the *Mysore Gazette* dated 21st September 1916, calling for tenders for resorting Kanagal Hirikere and Kanhikere, Registered No. 871 of Hunsur Taluk, Mysore District.

Notice.

The attention of the public is invited to the advertisement in detail published in the *Mysore Gazette* dated 21st September 1916, calling for tenders for restoring the Hongañahalli (Kommarahalli) tank, registered No. 15 of Mandya Taluk, Mysore District.

Notification dated 15th September 1916.

A sum of Rs. 23-13-0 due to one Haliah for metalling bad portions of Yedatore-Ramanathapur road lies unclaimed in the accounts of this office since July 1915. If this amount is not claimed by the party or his heirs within three months from this date, the same will be credited to Government.

Y. ASWATHNARAYANA ROW,
Executive Engineer.

HEADQUARTER RANGE, MYSORE.

A sum of Rs. 165-6-4 due to contractors Surathi Naik and Cheluvaroya Chetty on account of work done by them in the new Palace at Mysore is outstanding in the books of this office from February 1914, and notice is hereby given that if the parties do not apply to this office for payment before the end of October 1916, the amount will be credited to Government.

S. H. LAKSHMINARASAPPA,
Assistant Engineer.

SHIMOGA DIVISION.

Dated 15th September 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 12th October 1916, for restoring the Bhogi Vaddu in Shikarpur Taluk. An approximate estimate of quantities are given below. These quantities are not guaranteed. The work should be completed by the end of June 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 400 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for restoring Bhogi Vaddu in Shikarpur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of Bhogi Vaddu Tank estimate.

No.	Items of work	Per	Quantity
	BUND—		
1	Clearing jungle on the bund, throughout	L. S.	
2	Earthwork to bund	C. yd.	7,381
3	Turfing	C. yd.	4,008
4	Bund grade stones with bottom slabs	Each	65
5	Top width stones from Kodur	"	65
6	Bench mark stones, dressed and fixed	"	2
7	Register No. stones do	"	1
8	Gauge stones, numbered do	"	1
9	Removing silt in the breach and stopping	C. yd.	578
10	Puddle wall in centre of bund	"	102
11	Rough stone pitching in the breach	"	45
	Total Bund ...		
	SLUICE No. 1.—		
1	Earthwork excavating, cutting and refilling with watering and tamping, etc., complete.	C. yd.	288
2	Earthwork excavating, foundations	"	32
3	Concrete in surki mortar	C. ft.	288
4	Burnt brick in surki mortar	"	1,320
5	Do stone slabs, dressed and fixed	S. ft.	313
6	Plastering with surki mortar	Sqr.	10'30
7	Boring holes to upper orifice	L. S.	
8	Teakwood plug with rod	"	
9	Cast iron pipes, 10" diameter, carting, fixing, etc., complete	R. ft.	45
10	Blocking up old sluice	L. S.	
	Total ...		
	SLUICE No. 2.—		
	As per sluice No. 1 (see details above.)		
	Waste weir on left flank at C. S. 2 and R. L. 50'00.		
1	Clearing drafts and foundations to use the earth for the training bank...	C. yd.	6,350
2	Burnt brick in surki mortar	C. ft.	2,782
3	Do stone slabs, dressed and fixed from Kodur	S. ft.	733
4	Plastering with surki mortar	Sqr.	14'36
5	Rough stone work, new	C. yd.	346
	Total for weir ...		

V. R. NIJAGAL,
Executive Engineer.

COMPTROLLER'S OFFICE.

Notice No. 1943—*R.* 129, *dated 6th September* 1916.

1. Sealed tenders are invited for the supply to the Comptroller's Office, Bangalore, of some books on Accounts, Economics and Finance worth about Rs. 950, a detailed list of which can be seen in the Office.

2. The tenders should be superscribed "Tenders for the supply of books for the Comptroller's Office Library" and should give the rates at which the several classes of books will be delivered at this office, *viz.*, books published in India, books published in England or America, whose price is nett or otherwise, Government of India publications and Parliamentary publications. The tenders should reach the undersigned not later than 15th October 1916.

3. Each tenderer should deposit Rs. 25 in one of the Mysore State Treasuries or the Bank of Madras, Madras or Bangalore, and the Treasury or Bank receipt for such deposit should accompany the tender.

4. The undersigned does not bind himself to accept the lowest or any tender, or to assign reasons for rejecting any tender.

5. The deposit amount will be returned to the unsuccessful tenderers on application as soon as the result of the tenders is known. The successful tenderer will be furnished with a list of the books required which he should supply at the office of the undersigned within four months after the order for books required is placed. In the case of individual books a longer time will be given for supplying them on sufficient reason being shown.

6. The books may be ordered for and supplied in instalments. As soon as one or more books are supplied they will be paid for as per accepted rates, and the deposit amount will be returned as soon as all the books ordered are received.

7. If the undersigned should at any time consider that energetic steps are not taken to supply books in a reasonable time, the amount deposited will be forfeited and the order for the remaining books cancelled.

M. N. KRISHNA RAO,
Officiating Comptroller.